

C15

West Burton



Sector

Power Stations



Client

EDF

Contractor

Kier

Location

West Burton

Project Value

£560k

Status

Complete

Products

3 phase project with 800 metres of walkway and handrails per building, with 3 buildings, on a £3.9 Billion pounds project. Walkway originally designed in Galvanised steel, Quantum aluminium walkways were eventually the chosen material giving huge savings in both program and cost as the galv was penetrative and the aluminium is supported from roof profile. Completed on budget and within program of 22 weeks